

# MUNICIPALITY OF ANCHORAGE PURCHASING DEPARTMENT

PHONE (907) 343-4590 P.O. Box 196650 ANCHORAGE, ALASKA 99519-6650

DATE OF INVITATION <b>October 19, 2022</b>	TIME AND DATE OF OPENING <b>2:00 PM Local Time, November 9, 2022</b>
---	---

## ADDENDUM No. 1

TO INVITATION TO BID No. 2022C047

DATE ISSUED: November 2, 2022

TITLE: APD ELMORE BUILDING FF&E - WAREHOUSE

The following changes and/or additions are hereby made to subject Invitation to Bid:

- 1. CHANGE:** the Time and Date of BID OPENING to 2:00 PM Local Time, November 9, 2022.
- 2. INCORPORATE:** Questions & Answers, consisting of three pages, identified as Addendum No. 1.

All other terms, conditions and specifications remain unchanged.

An electronic (.pdf) copy of the Invitation to Bid is available at Municipality of Anchorage, Purchasing Office website; (<http://www.muni.org/Departments/purchasing/Pages/bidding.aspx>) Should you choose to obtain a copy of the Invitation to Bid from the website; it is your responsibility to periodically check the website for addends.

THIS ADDENDUM MUST BE ACKNOWLEDGED IN SPACE PROVIDED ON BID PROPOSAL SHEET OR SIGNED AND RETURNED TO PURCHASING PRIOR TO TIME SET FOR BID OPENING IN ACCORDANCE WITH ANCHORAGE MUNICIPAL CODE 7.20.020C.

Municipality of Anchorage reserves the right to accept or reject bids. Prices quoted must be F.O.B. Destination. Municipality is exempt from Federal Excise Tax. Bids shall be submitted to the Purchasing Office prior to time set for opening. Any bids not received by the Purchasing Office prior to that time will not be considered and will be returned.

PLEASE ACKNOWLEDGE AND RETURN THIS ADDENDUM PRIOR TO THE DATE AND TIME SHOWN ABOVE OR YOUR BID MAY BE REJECTED.

VENDOR NAME \_\_\_\_\_

MUNICIPALITY OF ANCHORAGE

SIGNATURE \_\_\_\_\_

*Chris Hunter*

DATE OF BID \_\_\_\_\_

Chris Hunter  
Deputy Purchasing Director

**Invitation to Bid 2022C047  
APD Elmore Evidence Shelving**

**Addendum No. 1  
November 2, 2022**

**TO: PLANHOLDERS**

The contract documents for the referenced project are clarified and amended as follows:

**Responses to Bidder's Questions**

**Question 1:** I noticed for the 381 each additional shelves, the dimension states 60" x 24". Should it not coincide with the 72" x 24" shelving units dimension wise?

**Answer 1:** *Sheet I103, Item code S2 particle board shelf, dimension shall read 72" x 24" in lieu of 60" x 24 and total quantity shall read 363 in lieu of 381.*

**Question 2:** RUB-1, rubber flooring tiles on sheet I103. What is the thickness desired for these tiles? You can get these in sizes ranging from 3/8" to 1".

**Answer 2:** *Sheet I103, Item code RUB-1 Rubber Flooring, model number shall read DZ00-black. Dimension shall read 36" x 36" square edge tiles, 8mm.*

**Question 3:** RUB-1, rubber flooring tiles on sheet I103. Please confirm the desired footprint is 22'x18' (sheet I102)? I only ask because the tiles are 3'x3' and 3' will go evenly into 18' but not 22'. I can cut a tile to get the 22' but want to ensure this was not an accidental typo for 21'.

**Answer 3:** *Sheet I102, dimension of RUB-1 shall read 24'-0" in lieu of 22'-0".*

**Question 4:** Sheet I103, S-2 in the equipment and material legend. Can you confirm the quantity of 127 units? I counted 121 units. Is the desire to over order to have extra in storage?

**Answer 4:** *Sheet I103, Item code S2 Heavy duty Boltless Shelving, total quantity shall read 121 in lieu of 127.*

**Question 5:** Sheet I103, S-2 in the equipment and material legend. Can you confirm the dimensions of particle board shelf TENNSCO 7E573 was intended to be 60"x24"? The shelving units are 72"x24" and it doesn't make sense to order extra shelves that would be smaller than what the racks are designed to hold.

**Answer 5:** see answer above.

**Question 6:** Sheet I103, S-2 in the equipment and material legend. Can you confirm the quantity of 381 extra shelves? I counted 121 rack units and that would equate to 362 extra shelves.

**Answer 6:** see answer above.

**Question 7:** During the site visit a sliding rack floor system was encountered where the proposed rubber flooring is to be installed. Is this system to be removed entirely and cavity filled with a subfloor?

**Invitation to Bid 2022C047  
APD Elmore Evidence Shelving**

**Addendum No. 1  
November 2, 2022**

**Answer 7:** *No, this in floor system is to remain and the plywood is to be fastened in place. The proposed rubber flooring will be installed over the existing plywood.*

**Question 8:** Is the entire sliding rack floor system to be covered with the new flooring? 18' from the wall to the column is adequate distance to cover the entire width of the floor rack system. However, 22' from the end wall (closet door side) is not far enough to cover the sliding rack flooring.

**Answer 8:** *Yes, refer to Addenda 1, answer 3.*

**Question 9:** Will seismic restraints be required to be installed with the shelving? Floor anchor plates can be purchased with these shelves and anchored into the concrete slab.

**Answer 9:** *Seismic restraints are not required.*

**Question 10:** If floor anchor plates are required, then how many/what spacing is required for adequate seismic resistance?

**Answer 10:** *See response above.*

**Question 11:** Sheet I102, Detail 1, shows some of the S-2 racks being installed back-to-back. Will a spacer plate be required to maintain a uniform separation distance on these 4 rows?

**Answer 11:** *A spacer plate is not required.*

**Question 12:** If a spacer plate is required, is the 8' aisle dimension on sheet I102, Detail 1, a minimum dimension that needs to be maintained?

**Answer 12:** *See response above.*

**Question 13:** Sheet I102, Detail 1, there is a thermostat and other assorted plugs/controls located on the back side of the bathroom wall. Is it acceptable to set shelving height to any level that would prevent a conflict with the thermostat and maintain user access?

**Answer 13:** *Yes.*

**Question 14:** Sheet I102, Detail 2, the gun room has a couple fire alarms that sit a little low on the wall. The 84" shelves would interfere with these if they were pushed flushed against the wall. Is it acceptable to offset the shelves that conflict with fire alarms away from the wall?

**Answer 14:** *Yes.*

**Question 15:** Are the 3 extra shelves per rack to include all necessary accessories to create a new shelf space or are the 3 extra shelves per rack only the particle board panel with no accessories?

**Answer 15:** *The 3 extra shelves per rack are to include all accessories required to create a new shelf space.*

**Question 16:** Is a general contractor license required for this job?

**Answer 16:** *No.*

**Invitation to Bid 2022C047  
APD Elmore Evidence Shelving**

**Addendum No. 1  
November 2, 2022**

**Question 17:** Are footplates and anchoring to the concrete floor required?

**Answer 17:** *Refer to Answer 9.*

**Question 18:** What shelving weight capacity is required for each shelf?

**Answer 18:** *Minimum of 2000 lbs.*

**Question 19:** If anchoring is required is there in floor heating in the three rooms?

**Answer 19:** *Refer to Answer 9, there is no floor heating in these rooms.*

END OF ADDENDUM NO. 1