

MUNICIPALITY OF ANCHORAGE PURCHASING DEPARTMENT

PHONE (907) 343-4590 P.O. Box 196650 ANCHORAGE, ALASKA 99519-6650

DATE OF INVITATION December 27, 2022	TIME AND DATE OF OPENING 2:00 PM Local Time, January 31, 2023
--	---

ADDENDUM No. 2

TO INVITATION TO BID No. 2022C051

DATE ISSUED: January 6, 2023

TITLE: AREAWIDE PARK, TRAIL, AND PARK FACILITY IMPROVEMENTS.

The following changes and/or additions are hereby made to subject Invitation to Bid:

1. **INCORPORATE:** the attached changes, consisting of six pages, identified as Addendum No. 2, dated January 6, 2023.

All other terms, conditions and specifications remain unchanged.

An electronic (.pdf) copy of the Invitation to Bid is available at Municipality of Anchorage, Purchasing Office website; (<http://www.muni.org/Departments/purchasing/Pages/bidding.aspx>) Should you choose to obtain a copy of the Invitation to Bid from the website; it is your responsibility to periodically check the website for addends.

THIS ADDENDUM MUST BE ACKNOWLEDGED IN SPACE PROVIDED ON BID PROPOSAL SHEET OR SIGNED AND RETURNED TO PURCHASING PRIOR TO TIME SET FOR BID OPENING IN ACCORDANCE WITH ANCHORAGE MUNICIPAL CODE 7.20.020C.

Municipality of Anchorage reserves the right to accept or reject bids. Prices quoted must be F.O.B. Destination. Municipality is exempt from Federal Excise Tax. Bids shall be submitted to the Purchasing Office prior to time set for opening. Any bids not received by the Purchasing Office prior to that time will not be considered and will be returned.

PLEASE ACKNOWLEDGE AND RETURN THIS ADDENDUM PRIOR TO THE DATE AND TIME SHOWN ABOVE OR YOUR BID MAY BE REJECTED.

VENDOR NAME _____
ANCHORAGE

MUNICIPALITY OF

SIGNATURE _____

Chris Hunter

DATE OF BID _____

Chris Hunter
Deputy Purchasing Director

**Invitation to Bid PROJECT#2022C051
Areawide Park, Trail, and Park Improvements**

**Addendum No.2
January 6, 2023**

TO: PLANHOLDERS

The contract documents for the referenced project are clarified and amended as follows:

MODIFICATIONS/CLARIFICATIONS:

MODIFICATIONS/SPECIAL PROVISIONS:

BID PROPOSAL MODIFICATIONS:

Item No. 1: **REPLACE** Bid Proposal Sheet BP-3 of BP-7 through BP-7 of BP-7 with the attached Bid Proposal Sheet **BP3R-BP7R through BP7R-BP7R**, identified as Addendum No. 2, dated January 6, 2023.

DRAWINGS:

RESPONSES TO BIDDERS' QUESTIONS:

Question 1: A-12 has LF for the unit of measurement, it should be SY like the description 0 to 500 SY.

Response: This is correct, it has been changed to SY.

Question 2: A-23 and A-24 have a unit of measurement of tons. Typically, geo-fabrics are measured by the SY.

Response: This is correct. Geofabric quantity type has been changed to SY.

Question 3: A-45 line item number is used twice for two different activities.

Response: This is a typo; numbering has been corrected.

Question 4: Boulders (Small 3x3x3) is on the bid schedule twice.

Response: Item A-76 has been changed to the following: Boulder (Medium, 4x4x4) per Each.

Where any requirements of the Invitation to Bid conflict with an item in an Addendum, the Addendum shall govern. All other terms and conditions of the Invitation to Bid shall remain unchanged and in full force and effect.

END OF ADDENDUM NO.2

**MUNICIPALITY OF ANCHORAGE
PARKS AND RECREATION DEPARTMENT**

**AREAWIDE PARK, TRAIL AND PARK FACILITY IMPROVEMENTS 2023
Project No. 07-52**

ITEM NO.	SPEC. NO.	WORK DESCRIPTION	ESTIMATED QUANTITY	UNIT BID PRICE	TOTAL BID PRICE
A-1	20.02	Storm Water Pollution Prevention Plan (SWPPP) Type 1 per LS	1		
A-2	20.04	Clearing & Grubbing per Acre	1		
A-3	20.05	Clearing for bike trail/sidewalk/curb ramp per L.F.	100		
A-4	20.06	Tree Removal, 0 to 5 Each per Each	5		
A-5	20.06	Tree Removal, Over 5 Each per Each	10		
A-6	20.07	Remove of Sidewalk per S.Y.	200		
A-7	20.08	Remove Curb and Gutter, 0 to 50 L.F. per L.F.	50		
A-8	20.09	Remove Pavement, 0 to 200 S.Y. per S.Y.	200		
A-9	20.10	Usable Excavation (Truck Count), over 150 C.Y. per C.Y.	200		
A-10	20.10	Unusable Excavation (Truck Count), 0 to 150 C.Y. per C.Y.	100		
A-11	20.10	Unusable Excavation (Truck Count), over 150 C.Y. per C.Y.	200		
A-12	20.11	Grading Existing Surfaces, 0 to 500 S.Y. per S.Y.	500		
A-13	20.18	Filter Rock per Ton	50		
A-14	20.18	Drain Rock per Ton	50		
A-15	20.20	Unclassified Fill and Backfill per C.Y.	50		
A-16	20.21	Classified Fill and Backfill (Type II-A), over 100 Ton per Ton	200		
A-17	20.22	Leveling Course, 1-50 Ton per Ton	50		
A-18	20.22	Leveling Course, >50 Ton per Ton	75		

**MUNICIPALITY OF ANCHORAGE
PARKS AND RECREATION DEPARTMENT**

**AREAWIDE PARK, TRAIL AND PARK FACILITY IMPROVEMENTS 2023
Project No. 07-52**

ITEM NO.	SPEC. NO.	WORK DESCRIPTION	ESTIMATED QUANTITY	UNIT BID PRICE	TOTAL BID PRICE
A-19	20.23	Cobbles per Ton	50		
A-20	20.24	Rip Rap (Class I), 0 to 25 Ton per Ton	25		
A-21	20.24	Rip Rap (Class II), 0 to 25 Ton per Ton	25		
A-22	20.24	Rip Rap (Class III), 0 to 25 Tons per Ton	25		
A-23	20.24	Geotextile (Type-A Separation) per S.Y.	25		
A-24	20.24	Geotextile (Type-C Drainage) per S.Y.	25		
A-25	20.25	Insulation Board (R=18), > 1000 S.F. per SF	1,000		
A-26	30.02	P.C.C. Curb and Gutter (Type 7 - Play Curb), 0 to 50 L.F. per L.F.	50		
A-27	30.02	P.C.C. Curb and Gutter (Type 7 - Play Curb), > 50 L.F. per L.F.	100		
A-28	30.03	P.C.C. Sidewalk, 4" Thick, Standard Finish, 0 to 25 S.Y. per S.Y.	25		
A-29	30.03	P.C.C. Sidewalk, 4" Thick, Exposed Aggregate Finish, 0 to 25 S.Y. per S.Y.	25		
A-30	30.05	P.C.C. Structure Retaining Wall (Class A-3), 0 to 25 C.Y. per CY	25		
A-31	30.09	Concrete Parking Bumpers (7' Long) per Each	10		
A-32	30.11	Sidewalk Joint Sealant, 0 to 50 L.F. per L.F.	50		
A-33	40.02	Asphalt for Seal Coat, 0 to 20 Ton per Ton	20		
A-34	40.02	Cover Aggregate, 0 to 20 Ton per Ton	20		
A-35	40.04	Asphalt for Tack Coat, 0 to 5 Ton per Ton	5		

**MUNICIPALITY OF ANCHORAGE
PARKS AND RECREATION DEPARTMENT**

**AREAWIDE PARK, TRAIL AND PARK FACILITY IMPROVEMENTS 2023
Project No. 07-52**

ITEM NO.	SPEC. NO.	WORK DESCRIPTION	ESTIMATED QUANTITY	UNIT BID PRICE	TOTAL BID PRICE
A-36	40.05	Crack and Joint Sealant, > 1,000 L.F. per L.F.	100		
A-37	40.06 95.04	A.C. Pavement (Class D, 2" Thickness), 1 - 100 Ton per Ton	20		
A-38	40.06 95.04	A.C. Pavement (Class D, 2" Thickness), 101 - 500 Ton per Ton	50		
A-39	40.06 95.04	A.C. Pavement (Class D, 2" Thickness), > 500 Ton per Ton	50		
A-40	40.06 95.04	A.C. Pavement (Class E, 2" Thickness), 1 - 100 Ton per Ton	20		
A-41	40.06 95.04	A.C. Pavement (Class E, 2" Thickness), 101 - 500 Ton per Ton	50		
A-42	40.06 95.04	A.C. Pavement (Class E, 2" Thickness), >500 Ton per Ton	50		
A-43	40.11	Remove and Replace Asphalt Surfacing (Class D) per SY	50		
A-44	55.03	Furnish & Install Subdrain (4" Perforated CPEP, Type D Filter Material, Type C Geotextile Fabric) per LF	50		
A-45	55.20	Furnish & Install Culvert with End Sections (18" CMP) per LF	30		
A-46	65.02	2 Person Survey Crew per Hour	40		
A-47	70.10	Traffic Marking 4" White per LF	100		
A-48	70.10	Traffic Marking 4" Yellow per L.F.	100		
A-49	70.10	Traffic Marking, 4" Blue per L.F.	100		
A-50	70.10	Traffic Marking, Blue ADA Symbol, 0 to 5 per Each	1		
A-51	70.13	Furnish & Install Wood Bollard per Each	1		
A-52	70.13	Furnish & Install Removable Steel Rectangular Bollard per Each	1		
A-53	70.22 95.04	One Person Labor Crew per Hour	50		

MUNICIPALITY OF ANCHORAGE
PARKS AND RECREATION DEPARTMENT

AREAWIDE PARK, TRAIL AND PARK FACILITY IMPROVEMENTS 2023

Project No. 07-52

ITEM NO.	SPEC. NO.	WORK DESCRIPTION	ESTIMATED QUANTITY	UNIT BID PRICE	TOTAL BID PRICE
A-54	70.22 95.04	Two Person Labor Crew per Hour	40		
A-55	70.23 95.04	Sawcut Asphalt or Concrete, 0 to 100 per L.F.	100		
A-56	70.24 95.04	Rootwad Bank Stabilization per LF	50		
A-57	70.25 95.04	Install Owner Supplied Park Bench per Each	5		
A-58	70.25 95.04	Install Owner Supplied Trash Receptacle per Each	5		
A-59	70.25 95.04	Install Owner Supplied Picnic Table per Each	5		
A-60	75.02	Perennial (1 gallon container) per Each	50		
A-61	75.02	Shrubs (12" Ht.) per Each	20		
A-62	75.02	Shrubs (18" Ht.) per Each	20		
A-63	75.02	Shrubs (24" Ht.) per Each	20		
A-64	75.02	Trees Picea pungens 'Glauca' (5'-6' Ht.) per Each	20		
A-65	75.02	Trees Populus tremuloides 'Erecta' (3" Caliper) per Each	15		
A-66	75.02	Trees Betula papyrifera (2.5" Caliper) per Each	15		
A-67	75.02 95.04	Bark Mulch (3-inch depth) per 1,000 S.F.	5		
A-68	75.03	Topsoil (2" Thick) per 1,000 S.F.	5		
A-69	75.03	Topsoil (4" Thick) per 1,000 S.F.	5		
A-70	75.03	Topsoil (18" Depth) per 1,000 S.F.	5		
A-71	75.04	Seeding (schedule A) per 1,000 S.F.	10		
A-72	75.04	Seeding (Schedule B) per 1,000 S.F.	10		
A-73	75.04	Seeding (schedule C) per 1,000 S.F.	10		

**MUNICIPALITY OF ANCHORAGE
PARKS AND RECREATION DEPARTMENT**

**AREAWIDE PARK, TRAIL AND PARK FACILITY IMPROVEMENTS 2023
Project No. 07-52**

ITEM NO.	SPEC. NO.	WORK DESCRIPTION	ESTIMATED QUANTITY	UNIT BID PRICE	TOTAL BID PRICE
A-74	75.04	Seeding (schedule D) per 1,000 S.F.	10		
A-75	75.10	Concrete Modular Block per S.F.	100		
A-76	75.11	Boulder (Medium, 4x4x4) per Each	20		
A-77	75.11	Boulder (Small, 3x3x3) per Each	20		
A-78	75.12 95.04	Wood Fiber Safety Surfacing per CY	50		

TOTAL SCHEDULE A: \$ _____ -

CONTRACTOR _____

DATE _____